




- GENERAL ELECTRICAL NOTES:
- A. COORDINATE THE CONNECTIONS OF ALL EQUIPMENT PROVIDED BY OTHERS WITH THE CONTRACTOR PROVIDING THE EQUIPMENT PRIOR TO ROUGH-IN. THIS INCLUDES, BUT IS NOT LIMITED TO, MECHANICAL EQUIPMENT, KITCHEN EQUIPMENT, AUDIO/VISUAL EQUIPMENT, FIRE SUPPRESSION SYSTEM EQUIPMENT, FIRE ALARM EQUIPMENT, ETC. THE ELECTRICAL CONTRACTOR IS RESPONSIBLE TO PROVIDE THE APPROPRIATE DISCONNECTING MEANS FOR, AND TO MAKE THE FINAL CONNECTION TO, ANY HARDWIRED EQUIPMENT. THE ELECTRICAL CONTRACTOR IS ALSO RESPONSIBLE TO PROVIDE AN APPROPRIATE CORD AND PLUG FOR ANY CORD-AND-PLUG CONNECTED EQUIPMENT THAT IS NOT EQUIPPED WITH AN INTEGRAL CORD AND PLUG.
- B. ALL EQUIPMENT, DEVICES, AND LUMINAIRES SHALL BE SUITABLE FOR THE ENVIRONMENT IN WHICH THEY ARE INSTALLED. EQUIPMENT MOUNTED OUTDOORS SHALL BE NEMA 3R. DEVICES MOUNTED IN DAMP OR WET LOCATIONS SHALL BE WEATHERPROOF. RECEPTACLES RATED 15- OR 20-AMPS AND 120 VOLTS WHICH ARE LOCATED IN DAMP OR WET LOCATIONS SHALL BE GFCI PROTECTED AND EQUIPPED WITH A SUITABLE WEATHERPROOF COVERPLATE (WHILE-IN-USE IN WET LOCATIONS).
- C. ALL LUGS, TERMINALS, ETC. IN ELECTRICAL DISTRIBUTION EQUIPMENT SHALL BE LISTED FOR A MINIMUM OF 75 DEGREE C CONDUCTORS. TERMINATIONS LISTED FOR ONLY 60 DEGREE C CONDUCTORS ARE NOT PERMITTED.

- KEYED NOTES:
1. DISCONNECT SWITCH IS PROVIDED BY EQUIPMENT MANUFACTURER INTEGRAL WITH EQUIPMENT. THE ELECTRICAL CONTRACTOR SHALL PROVIDE CIRCUIT AND FINAL CONNECTION TO DISCONNECT SWITCH AS INDICATED.
2. WEATHERPROOF GFCI SERVICE RECEPTACLE IS PROVIDED BY EQUIPMENT MANUFACTURER INTEGRAL WITH EQUIPMENT. THE ELECTRICAL CONTRACTOR SHALL PROVIDE CIRCUIT AND FINAL CONNECTION TO SERVICE RECEPTACLE AS INDICATED.
3. DUCT SMOKE DETECTOR AND RELAY FOR HVAC UNIT SUPPLY FAN SHUTDOWN SHALL BE FURNISHED BY THE ELECTRICAL CONTRACTOR FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. THE ELECTRICAL CONTRACTOR SHALL ALSO PROVIDE A REMOTE KEYED TEST STATION WITH VISUAL STATUS ANNUNCIATOR WHEN DUCT SMOKE DETECTOR IS INSTALLED IN A CONCEALED LOCATION GREATER THAN 10'-0" ABOVE FINISHED FLOOR OR WHEN DUCT SMOKE DETECTOR'S STATUS INDICATORS ARE NOT READILY VISIBLE. COORDINATE LOCATION OF REMOTE KEYED TEST STATION WITH AUTHORITY HAVING JURISDICTION AND OWNER PRIOR TO ROUGH-IN. ALL FINAL WIRING SHALL BE BY THE ELECTRICAL CONTRACTOR.
4. CONNECT EXHAUST FAN TO LIGHTING CIRCUIT SERVING THE RESTROOM. SEE SHEET E-101 FOR CONTINUATION.
5. STARTER IS FURNISHED BY HOOD SUPPLIER IN HOOD MASTER CONTROL PANEL. MAKE FINAL CONNECTION THROUGH HOOD MASTER CONTROL PANEL.



ELECTRICAL ROOF PLAN

1/4"



PAUL DHANENS • ARCHITECT

ARCHITECT	
<div><div><div>PAUL DHANENS</div><div>NO. C-23843</div><div>GENERAL</div><div>STATE OF CALIFORNIA</div></div><div>5100 CALIFORNIA AVE, SUITE 107 BAKERSFIELD, CALIFORNIA 93309 TELEPHONE: (661) 326-8935 FACSIMILE: (661) 326-8937</div></div>	
CONSULTANT	
COPYRIGHT	
<p>PAUL DHANENS ARCHITECT expressly reserves its copyright and other property rights in these documents which are not to be reproduced, changed or copied in any written, graphic or electronic form, nor adapted to any third party without the expressed written consent of PAUL DHANENS ARCHITECT.</p> <p>NOTICE TO CONTRACTORS: Written dimensions on these drawings shall take precedence over scaled dimensions. Contractor shall verify and be responsible for confirming all dimensions and shall notify the architect immediately of any discrepancies or field variations discovered.</p>	
PROJECT	
TENANT IMPROVEMENT FOR	
<div><div><div>FAMOUS FOR</div><div>Steak 'n Shake</div><div>STEAKBURGERS</div></div><div>1966 WEST AVE L LANCASTER, CA</div></div>	
DATE	ISSUED FOR
8-24-18	BUILDING DEPT SUBMITTAL
6-28-19	
NO.	REVISIONS
▲	
▲	
▲	
▲	
ELECTRICAL	
FILE NAME:	2366A2-0
SHEET	
E-301	